Specification BT-2000S

Solar Panel	2x440W - Mono
Panel Lifting	0°~45° Manual Lifting
LFP Battery	8.04 kWh 95% DoC
System Voltage	DC25.6V
Battery Charger	1.5KW, AC220V/110V
CCTV	2× TandemVu 6+4MP 25X ColorVu & IR Acusense Panoramic Network Speed Dome
Storage	4TB NVR, 36 days Storage
4G Router	Yes
Loud Speaker	Yes
LED Light	Optional (100W)
Wireless Bridge	Optional
Controller	40A MPPT
Mast & Height	5 Sections 6.5M
Mast Lifting	Manual Winch
Trailer Standard	US/AU/EU
Hitch	2" Ball
Brake	Electric
Axle	Single
Tire	14 inch
Outriggers	Optional
Lifting Ring	4 ×
Forklift Holes	4 ×
Working Temp	-20°C~60°C
Charging Time	8.6 hours
Running Time	4 days for 75W
Operating Dimension(mm)	3890*2250*7400
Weight	400kg
QTY in 20' / 40'	10 units / 20 units

CCTV System

TandemVu x 2   4TB NVR   4G Router   Loud Speaker   Display